

LEWEY LAKE CAMPGROUND SEQUENCED DOSING CHAMBER

As-built

All outlet inverts 4" off floor.

CueBox model: QB3-30. Trigger manifolds set at 30" above floor for 22" drawdown WITH 4" BUILT-ON SHOP

Flout models:

2- FL2231-QR-4R 3" single Flout w/ right hand CueBox tap.  
4" riser 22" drawdown

1-FL2231-QL-4R 3" single Flout w/ left hand CueBox tap.  
4" riser 22" drawdown

Maximum liquid depth 30-31"

Minimum liquid depth 8-9"

Drawdown 22"

Rissy Plastics, LLC  
350 Cedar Lane  
Torrington, CT 06790  
860-482-1645  
877-221-4426  
www.flout.net

FLOUT® US Pat. 5290434  
CueBox™ US Pat Pend  
©2010 Rissy Plastics, llc

